



westcon
precast inc.

BOAT RAMP SLAB
3m

CONCRETE	RELEASE 28 day 15 MPa 35 MPa	AIR 6-8%	SLUMP 75mm	TYPE 50
VOLUME	SELF WEIGHT			
0.17 m ³	400 kg	880 lbs		
DATE: FEB. 2015	CODE: 0600	BY: CW		

DWG. NO.
W9-01

Rev. **O**