



westcon
precast inc.

BOAT RAMP SLAB
4.2m

CONCRETE	RELEASE 28 day 15 MPa 35 MPa	AIR 6-8%	SLUMP 75mm	TYPE 50
VOLUME	SELF WEIGHT			
0.23 m ³	585 kg	1205 lbs		
DATE: FEB. 2015	CODE: 0200	BY: CW		

DWG. NO.
W9-00

Rev. **O**