

Site Readiness Guidelines

For Tank Deliveries



19 Riel Drive St. Albert
Alberta, T8N 3Z2

(780) 459-6695
sales@westconprecast.com

Site Readiness Checklist for Tank Deliveries

To ensure a smooth and efficient delivery, please review and adhere to the following site readiness guidelines before our picker trucks arrive.

Pathway and Access Requirements:

Ensure that the entire path to the installation site is clear of any obstructions, including vehicles, debris, or barriers.

- **Overhead Clearance:** The route should be free of overhead power lines, tree branches, and any other obstructions with at least 17 feet of clearance.
- **Access for Picker Truck:** Our picker truck requires a clear and accessible route, as well as a width of 17-20 feet for operation, including the extension of outriggers.
- **Reminder:** If a school bus can back up to the hole, there's enough space for our truck.



Hole Preparation:

- The hole for the tank should be pre-dug and positioned so that one face of the hole is open and accessible for the picker truck to back in.
- Confirm that the truck can back up directly to the hole without obstruction.



Final Checklist:

- ✓ Is the pathway clear and accessible for our picker truck?
- ✓ Overhead clearance of 17 feet is met?
- ✓ Width clearance of 17-20 feet is met?
- ✓ Hole is dug and ready with access?

Failure to meet these requirements may result in delivery delays or additional charges. Please contact us if you have any questions or concerns about site readiness before the scheduled delivery.

**For inquiries,
contact us.**

westcon
precast inc.

www.westconprecast.com
sales@westconprecast.com
(780) 459-6695

